

100-C-226 AS-BUILT LIGHTING PLANS

*(Adopted 04-17-12)*

The Contractor shall prepare two sets of as-built plans for the lighting portion of the contract. The as-built lighting plans shall be submitted to the Engineer no later than the end of the burn-in period for the luminaire.

Lighting as-built plans shall include a copy of the project title sheet and the plan sheets that show the lighting related work. The plans shall indicate the as-built location of light poles, high mast towers, electrical service, conduit runs, and lighting handholes.

The cost of as-built lighting plans shall be included in the cost of the lighting items.

---